Items	Per	Quantity	Rate	Cost
I. Bund—				
1. Earthwork including watering and tamping	C.yd.	5,470		
2. Turfing	S.yd.	4,359		
3. Cutting grips	No. of grade	30		
4. Jungle clearing (Prickly pear thick), cutting hongey trees and removing roots ...	,,	25		
5. New stone work	C.yd.	1,017		
6. Old stone work	,,	81		
7. Providing new grade stones with index stones with painting	No.	30		
8. Providing new B. M. stones	,,	2		
9. Do Registered No. stone and date stone with painting	,,	2		
II. Sluices 1 and 2—				
1. Cutting bund, examining and repairing the existing sluices with necessary masonry works	Each	2		
III. Waste Weir, left—				
1. Earthwork excavation	C.yd.	72		
2. Burnt brick in surki mortar	C.ft.	506		
3. Burnt stone slabs 6" thick	S.ft.	307		
4. Plastering with surki mortar	Sqr.	6·23		
5. Rough stone work new	C.yd.	43		
Total ...	...	...	...	...
Contingencies ...	...	...	...	...
Grand Total, Rupees ...	...	...	...	...

S. SRINIVASA IYER,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, SPECIAL DIVISION.

Notification dated 22nd August 1927.

"It is hereby notified for the information of the public that the Second Class Travellers Bungalow at Mysore will be closed to the public. The building ceases to be a Travellers Bungalow."

V. V. KARVE,
Executive Engineer.

MYSORE DISTRICT.

Notice No. 59, dated 20th August 1927.

Tenders are hereby invited for the supply of one waggon of charcoal and four waggons of fuel for the tunnel work at Hulikere, Mandya Taluk F. O. R. Byaderahally Railway Station within 15 days from the date of accepting the tender. Each tender should accompany with a deposit of Rs. 50 as earnest money.

If the same is not delivered within the prescribed time by the accepted tenderer, the deposit money will have to be forfeited.

B. KRISHNASWAMI IYENGAR,
Executive Engineer,
No. III Tunnel Division.